

Phase II: Timber Frame Project

Scope of work:

- 1) Mid west remove and replace
 - a. framing, rafters, roofboards, and roofing mat
- 2) Ramp repairs, sil replacement N. Barn
 - a. lift and support frame
 - b. repair ramp
 - c. replace sil and repair posts and siding
- 3) Sil & frame R+R S. Barn West
 - (same as above)
- 4) Floor and joist system Midwest R+R
 - prep lmd put in frame and floor
- 5) Lift and R+R sil beams Fix doors N. Barn
 - a. Road side & NW Corner
- 6) Timbore spray frames in all suspect areas
- 7) Siding- repair and/or replace- go over entire building